

**COMMONWEALTH OF PENNSYLVANIA
DEPARTMENT OF CONSERVATION AND NATURAL RESOURCES
HARRISBURG, PENNSYLVANIA**

**ADDENDUM NO. 1
TO BID DOCUMENTS FOR
CONTRACT NO. FDC-003-6194.1
GENERAL CONSTRUCTION
BRYNER MAINTENANCE HQ
TUSCARORA STATE FOREST
TOBOYNE TOWNSHIP, PERRY COUNTY, PENNSYLVANIA**

The Bidder is hereby advised of the following changes to the Bid Documents issued October 19, 2016, Bid Opening: 2:00 P.M., November 17, 2016.

1. Reference the Technical Specifications:

- a. Section 01 1000, SUMMARY, Page 01 1000-4, Paragraph 1.02.A.1: Add paragraph 1.02.A.1.c to read, "Installation of pellet storage silo, auger, feed tube, and associated materials and equipment to store and supply wood pellets to the boiler."
- b. Section 01 1000, SUMMARY, Page 01 1000-4, Paragraph 1.02.A.1.a: Change to read, "Construction of a new structurally-insulated panel Maintenance Building with mezzanine, complete with associated site work, including paving, site improvements, erosion and sedimentation control measures, site utility installation (except electrical and tele/data), and earthwork including trench excavation, overexcavation for engineered fill, and backfill for site utilities (except electrical and tele/data)."
- c. Section 01 1000, SUMMARY, Page 01 1000-4, Paragraph 1.02.B.1.a.i: Change to read, "Installation of dual-fuel boiler." By deleting the words, "and associated pellet storage silo".
- d. Section 01 1000, SUMMARY, Page 01 1000-5, Paragraph 1.02.D.1: Add Paragraph 1.02.D.1.h to read, "Electrical utility and site tele/data installation including trench excavation and backfill."
- e. Section 08 7340, OVERHEAD SECTIONAL DOOR OPENERS, Page 08 7340-2: Add Paragraph 1.10:

1.10 CONTRACT RESPONSIBILITY

- A. General Construction Contract FDC-003-6194.1 shall furnish and install all materials and components related to the overhead sectional doors, openers, and controls.

B. Electrical Construction Contract FDC-003-6194.4 shall furnish and install the electrical circuit connection to the overhead sectional door opener.

- f. Section 13 3419, METAL BUILDING SYSTEMS, Page 13 3419-6, Paragraph 3.08: Add paragraph 3.08.B to read, "Payment for all work performed under this section under Contract #FDC-003-6194.2 shall be considered incidental and payment shall be made under other sections of this specification."
- g. Section 31 2000, EARTHWORK, Page 31 2000-7, Paragraph 3.03.B: Delete this paragraph and all sub-paragraphs in their entirety. All excavation is unclassified per paragraph 3.03.A.
- h. Section 31 2000, EARTHWORK, Page 31 2000-14, Paragraph 3.18.B: Change to read, "Excess satisfactory soil material to be reused on the project may be temporarily stockpiled at a designated site chosen by the Department in accordance with the erosion and sediment control plan. All excess material not reused on the project shall be removed from the site."

2. Reference the Contract Drawings:

- a. Drawing S-101: MAINTENANCE BUILDING FOUNDATION/SLAB-ON-GRADE PLAN -- Change note referencing silo to read, "SILO & CONNS BY GENERAL CONTRACTOR".
- b. Drawing A-701: FINISH LEGEND -- Change FRP-1 size to 2'x2'.


3. The Bid Opening is being changed to November 29, 2017.

A COPY OF THIS ADDENDUM MUST BE SIGNED BY THE BIDDER AND ATTACHED TO THE BID FORM. FAILURE TO DO SO MAY RESULT IN REJECTION OF YOUR BID.

Bidder: _____

Date: _____

If your bid has been delivered prior to receiving this Addendum, telegraphic notification of revision of bid or of receipt of this Addendum will be accepted. Telegraphic modification shall not reveal the amount of the original or revised bids.



Alfred Uzokwe, Sr., P.E.

Director

Bureau of Facility

Design and Construction

Addendum No. 1

Issued: November 15, 2016