

2 LOCKER ROOM/ARMORY AREA DEMOLITION PLAN

SCALE: 1/8" = 1'-0"

0 4' 8' 16'

PROJECT NORTH



1 CENTRAL BOOKING AREA DEMOLITION PLAN

SCALE: 1/8" = 1'-0"

0 4' 8' 16'

PROJECT NORTH

GENERAL NOTES

1. CONTRACTOR SHALL REMOVE ALL EXISTING LIGHTING FIXTURES AND CONTROL DEVICES THAT ARE SHOWN ON THIS DRAWING. EXISTING FIXTURES THAT ARE NOT SHOWN ARE TO REMAIN. DISCONNECT CONDUCTORS/CABLES AND MAKE SAFE FOR REUSE TO NEW FIXTURES IN THE SAME GENERAL AREA.
2. CONTRACTOR SHALL REMOVE ALL EXISTING RECEPTACLES, SYSTEMS DEVICES, AND FIRE ALARM DEVICES THAT ARE SHOWN ON THIS DRAWING, WHICH ARE EITHER LOCATED IN WALLS TO RE REMOVED, OR OBSTRUCTING NEW CONSTRUCTION. CONTRACTOR SHALL VERIFY THAT RECEPTACLES AND DEVICES SHOWN ARE TRULY LOCATED IN WALLS TO BE REMOVED. IF NOT, THEY CAN REMAIN. EXISTING CIRCUITS WILL CONTINUE TO FEED RECEPTACLES REMAINING AS WELL AS NEW RECEPTACLES IN THE SAME GENERAL AREAS. EXISTING RECEPTACLES AND DEVICES NOT SHOWN ARE TO REMAIN.
3. DEMOLITION DRAWINGS ARE BASED ON AS-BUILT DRAWINGS AND ARE APPROXIMATE. CONTRACTOR SHALL VISIT PROJECT LOCATION PRIOR TO BIDDING TO CONFIRM FIXTURE AND DEVICE COUNTS AS WELL AS ACTUAL FIELD LOCATIONS.
4. SEE ARCHITECTURAL DEMOLITION DRAWINGS FOR INFORMATION ON WALLS AND OTHER STRUCTURES TO BE REMOVED.

KEY NOTES (#)

1. EXISTING CEILINGS IN THESE ROOMS ARE BEING ADJUSTED TO FACILITATE INSTALLATION OF NEW CORRIDORS. THE ELECTRICAL CONTRACTOR SHALL RELOCATE EXISTING FIXTURES IN THESE ROOMS TO MATCH ADJUSTED GRID.
2. REPLACE LIGHT SWITCH IN THIS LOCATION WITH NEW TO MATCH STYLE AND TYPE OF ALL OTHER NEW LIGHT SWITCHES AS SPECIFIED IN THE RENOVATIONS.
3. LIGHTING CONTROL PANEL TO REMAIN. SEE E-101 FOR A LISTING OF CIRCUITS THAT WILL CONTINUE TO BE CONTROLLED THROUGH THIS PANEL.
4. PRIOR TO CONSTRUCTION OF CORRIDOR, THE ELECTRICAL CONTRACTOR SHALL DISCONNECT ALL DEVICES, OTHER THAN RECEPTACLES, ON THIS WALL AND RETAIN FOR REINSTALLATION. ONCE CORRIDOR IS COMPLETE, INSTALL ON NEW WALL FACING EXISTING CLASSROOM/MULTIPURPOSE ROOM. EXTEND ALL CIRCUITS AND CONTROL OR DATA WIRING TO NEW LOCATIONS.
5. DISCONNECT LIGHT FIXTURE AT ROOF FOR REUSE. EXTEND CIRCUIT TO LOCATION SHOWN ON E-101.
6. DISCONNECT CAMERA IN THIS LOCATION FOR REUSE. EXTEND CONDUIT AND SIGNAL/COMMUNICATIONS CABLING TO NEW LOCATION SHOWN ON E-121. COUNTY'S VENDOR WILL PROVIDE SPECIFIC CAMERA HEIGHT AND FINAL CONNECTION.

KEY PLAN

ISSUED FOR BID

BUCHART HORN ARCHITECTS

M.E.P./F.P.S.
Buchart Horn Architects
445 West Philadelphia Street
York, PA 17401
717.854.1800

CIVIL
GLACE Associates, Inc.
38 North Duke Street
York, PA 17401
717.854.4805

ARCHITECT
Buchart Horn Architects
445 West Philadelphia Street
York, PA 17401
717.854.1800

STRUCTURAL
Buchart Horn Architects
445 West Philadelphia Street
York, PA 17401
717.852.1400

YORK COUNTY CENTRAL BOOKING RELOCATION
3400 CONCORD ROAD
YORK, PA 17402
SPRINGETTSBURY TOWNSHIP, YORK COUNTY

YORK COUNTY BOARD OF COMMISSIONERS
28 EAST MARKET STREET
YORK, PA 17401

REVISIONS

MARK	ISSUED DATE	DESCRIPTION

PROJECT NO:	77332-07
ISSUED DATE:	03/27/23
DRAWN BY:	TEB
CHECKED BY:	CLM

© BUCHART HORN, INC.

SHEET TITLE:

ELECTRICAL DEMOLITION PLANS

SHEET NO:

E-011

J:\PROJ\77332-07\06-CAD\15-ELECTRICAL\77332E_E-011.DWG Layout:E-011 03/27/2023 11:51 AM Miller, Corey