

2 LOCKER ROOM/ARMORY AREA FIRE ALARM PLAN

SCALE: 1/8" = 1'-0"

0 4' 8' 16'

PROJECT NORTH



1 CENTRAL BOOKING AREA FIRE ALARM PLAN

SCALE: 1/8" = 1'-0"

0 4' 8' 16'

PROJECT NORTH

GENERAL NOTES

1. SEE FIRE ALARM SYSTEM DIAGRAM ON SHEET E-XXX.
2. PROVIDE A COMPLETE AND OPERABLE FIRE ALARM SYSTEM TO COMPLY WITH ALL REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION.
3. FIRE ALARM DEVICES IN THE CENTRAL BOOKING AREA SHALL BE CONNECTED TO THE FIRE ALARM EXTENDER PANEL IN ELEC/DATA A128F. NEW FIRE ALARM DEVICES IN THE ARMORY/LOCKER ROOM AREA SHALL BE CONNECTED TO THE EXISTING INITIATION AND NOTIFICATION CIRCUITS FOR THAT AREA.
4. COORDINATE CEILING MOUNTED WORK WITH THE ARCHITECTURAL REFLECTED CEILING PLANS AND OTHER TRADES BEFORE PROCEEDING WITH ANY WORK. WHERE CONFLICTS OCCUR, NOTIFY THE ARCHITECT.
5. SEE SHEET G-XXX FOR BUILDING OCCUPANCY, CONSTRUCTION TYPE, AND OTHER INFORMATION.

KEY NOTES (#)

1. DUCT SMOKE DETECTOR, PROVIDE AND INSTALL PER DETAIL ON DRAWING E-501 AND PER MANUFACTURER REQUIREMENTS.
2. SMOKE DAMPER, PROVIDE AND INSTALL PER MANUFACTURER REQUIREMENTS.
3. PROVIDE CONNECTIONS BETWEEN SMOKE CONTROL PANEL AND FIRE ALARM EXTENDER PANEL. SEE DESCRIPTION ON SMOKE CONTROL SYSTEM AND MECHANICAL CONTROLS ON SHEET M-531 TO DEVELOP LIST OF SIGNALS REQUIRED. PROVIDE 2 #14 WITH #14 GRD FOR EACH SIGNAL. PROVIDE APPROPRIATELY SIZED CONDUIT FOR TOTAL WIRES REQUIRED. PROVIDE COLOR CODING AND LABELING TO MATCH THOSE OF ALL OTHER FIRE ALARM SYSTEM CONDUITS.
4. CONNECT FIRE ALARM EXTENDER PANEL TO MAIN FACILITY FIRE ALARM SYSTEM VIA MANUFACTURER RECOMMENDED CONDUCTORS OR CABLING IN CONDUIT. MAIN FIRE ALARM SYSTEM IS LOCATED IN IN EQUIPMENT ROOM E104. THE LOCATION OF E104 IS SHOWN IN THE KEY PLAN ON THIS SHEET.

KEY PLAN



ISSUED FOR BID

BUCHART HORN ARCHITECTS

M.E.P./F.P.E.
Buchart Horn Architects
445 West Philadelphia Street
York, PA 17401
717.854.1805

CIVIL
GLACE Associates, Inc.
38 North Duke Street
York, PA 17401
717.854.4805

ARCHITECT
Buchart Horn Architects
445 West Philadelphia Street
York, PA 17401
717.854.1805

STRUCTURAL
Buchart Horn Architects
445 West Philadelphia Street
York, PA 17401
717.852.1400

YORK COUNTY CENTRAL BOOKING RELOCATION
3400 CONCORD ROAD
YORK, PA 17402
SPRINGETTSBURY TOWNSHIP, YORK COUNTY, PENNSYLVANIA

YORK COUNTY BOARD OF COMMISSIONERS
28 EAST MARKET STREET
YORK, PA 17401

REVISIONS MARK	ISSUED DATE	DESCRIPTION

PROJECT NO:	77332-07
ISSUED DATE:	03/27/23
DRAWN BY:	TEB
CHECKED BY:	CLM

© BUCHART HORN, INC.

SHEET TITLE:

FIRST FLOOR FIRE ALARM PLANS

SHEET NO:

E-131

J:\PROJ\77332-07\08-CAD\1-5-ELEC\TRICAL\77332007_E-131.DWG Layout:(1)(2)2023 11:12 AM Mike_Caley