

2 LOCKER ROOM/ARMORY AREA SECURITY SYSTEMS PLAN

SCALE: 1/8" = 1'-0"

0 4' 8' 16'

PROJECT NORTH



1 CENTRAL BOOKING AREA SECURITY SYSTEMS PLAN

SCALE: 1/8" = 1'-0"

0 4' 8' 16'

PROJECT NORTH

GENERAL NOTES

1. FOR CARD READERS, DOOR CONTROLS, OTHER ACCESS CONTROL DEVICES, AND SECURITY CAMERAS, CONTRACTOR SHALL INSTALL DEDICATED PATHWAYS TO EACH DEVICE LOCATION SHOWN ON THIS PLAN FOR USE BY COUNTY'S SECURITY AND ACCESS CONTROL VENDOR(S). VENDOR(S) WILL PROVIDE CABLING, TERMINATIONS, DEVICES, IDF RACKS AND EQUIPMENT, CONTROL WORKSTATIONS AND SCREENS, TESTING, AND COMMISSIONING. ALL PATHWAYS SHALL BE ROUTED TO ELEC/DATA A128F UNO FOR THE ARMORY AREA.
2. VENDOR(S) ARE RESPONSIBLE FOR SYSTEM PROGRAMMING AND CONFIGURATION TO ACHIEVE DOOR CONTROL AND VIDEO MONITORING. THIS INCLUDES CONFIGURATIONS OF INTERLOCKING SCHEMES, OVERHEAD DOOR CONTROL METHODS, CAMERA ACTIVATION, WORKSTATION CONTROL, PRISON CENTRAL CONTROL OVERRIDES, ETC.
3. DOORS SHOWN TO HAVE ELECTRIC LOCKING MECHANISM WITHOUT A CARD READER ARE TO BE CONTROLLED FROM THE CENTRAL BOOKING CONTROL ROOM WORKSTATION UNO. ELECTRIC LOCK SYMBOL REPRESENTS ELECTRICAL ACTUATION ON SLIDING DOORS.
4. COORDINATE CEILING MOUNTED WORK WITH THE ARCHITECTURAL PLANS AND OTHER TRADES BEFORE PROCEEDING WITH ANY WORK. WHERE CONFLICTS OCCUR, NOTIFY THE ARCHITECT.

KEY NOTES (#)

1. CONTRACTOR SHALL PROVIDE PATHWAY FROM EXISTING IDFs IN LOCATION SHOWN TO ELEC/DATA A128F FOR VENDOR USE TO CONNECT NEW IDFs INTO EXISTING PRISON SYSTEMS. PROVIDE (2) 2" CONDUITS AT A MINIMUM.
2. CONTRACTOR SHALL PROVIDE DEDICATED PATHWAY FROM WORKSTATION LOCATIONS IN CENTRAL BOOKING CONTROL ROOM TO SECURITY AND ACCESS CONTROL HEAD END SYSTEMS WITHIN IDFs LOCATED IN ELEC/DATA A128F.
3. PROVIDE CONNECTION FROM EACH POWERED OVERHEAD DOOR CONTROLLER TO CENTRAL BOOKING CONTROL SYSTEM PANEL. PROVIDE MANUFACTURER'S RECOMMENDED CONTROL OR COMMUNICATION CABLING IN APPROPRIATELY SIZED CONDUIT.
4. RELOCATED CAMERA. SEE E-011 FOR MORE INFORMATION.
5. CONTROLLED DOORS IN THE ARMORY AREA ARE TO BE CONTROLLED FROM THE PRISON CENTRAL CONTROL ROOM.
6. ALL ITEMS LISTED IN GENERAL NOTES ABOVE FOR THE ARMORY AREAS ARE TO BE ROUTED INTO THIS ROOM WHICH CONTAINS EXISTING SECURITY AND ACCESS CONTROL IDFs.
7. EXISTING INTERCOM STATION IN PASSAGE SIDE OF NEW SLIDER DOOR IS EXISTING TO REMAIN. RELOCATE AS NECESSARY IF LOCATED IN WALL BEING RENOVATED.
8. THESE CARD READERS ARE CARD READER/FINGERPRINT UNITS.

KEY PLAN



ISSUED FOR BID

BUCHART HORN ARCHITECTS

M + P + E
Buchart Horn Architects
445 West Philadelphia Street
York, PA 17401
717.854.1800

CEL
CS Davidson, Inc.
38 North Duke Street
York, PA 17401
717.854.4805

ARCHITECT
Buchart Horn Architects
445 West Philadelphia Street
York, PA 17401
717.852.1400

STRUCTURAL
Buchart Horn Architects
445 West Philadelphia Street
York, PA 17401
717.852.1400

YORK COUNTY CENTRAL BOOKING RELOCATION

3400 CONCORD ROAD
YORK, PA 17402
SPRINGETTSBURY TOWNSHIP, YORK COUNTY

YORK COUNTY BOARD OF COMMISSIONERS

28 EAST MARKET STREET
YORK, PA 17401

REVISIONS MARK	ISSUED DATE	DESCRIPTION

PROJECT NO:	77332-07
ISSUED DATE:	03/27/23
DRAWN BY:	TEB
CHECKED BY:	CLM

© BUCHART HORN, INC.

SHEET TITLE:

FIRST FLOOR SECURITY SYSTEMS PLANS

SHEET NO:

E-121

J:\PROJ\77332-07\06-CAD\01-ELECTRICAL\77332007_E-121.DWG Layout:ISSUED 03/27/2023 11:52 AM Mike Carey