



1 COMPOSITE HANDHOLE DETAIL
NOT TO SCALE




- DUCT BANK NOTES
1. CONCRETE SHALL BE 3,000 P.S.I. @ 28 DAYS OR AS SPECIFIED.
 2. PROVIDE REINFORCING RODS ON TOP OF DUCTS WHEN CROSSING OR PLACING IN ROADWAYS.
 3. NON-FERROUS TIE WIRES TO BE IMBEDDED IN DUCT BED CONCRETE.

4 DUCT BANK SECTION
NOT TO SCALE



- DUCT BANK NOTES
1. CONCRETE SHALL BE 3,000 P.S.I. @ 28 DAYS OR AS SPECIFIED.
 2. PROVIDE REINFORCING RODS ON TOP OF DUCTS WHEN CROSSING OR PLACING IN ROADWAYS.
 3. NON-FERROUS TIE WIRES TO BE IMBEDDED IN DUCT BED CONCRETE.

2 DUCT BANK SECTION
NOT TO SCALE



3 TELECOMMUNICATION GROUNDING RISER DIAGRAM
NOT TO SCALE

RECORD REVISIONS			
PROFESSIONAL'S SIGNATURE DATE			
UpStreet ARCHITECTS, INC. 541 PHILADELPHIA ST. 911 MENOHER BLVD. INDIANA, PA 15701 JOHNSTOWN, PA 15905			
COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF GENERAL SERVICES HARRISBURG, PENNSYLVANIA			
D.G.S. PROJECT No. C-0588-0015 PHASE 1			
LOYSVILLE YOUTH DEVELOPMENT CENTER- RENOVATIONS TO ZIMMERMAN- BINGAMAN (ZB) COTTAGE DEPARTMENT OF HUMAN SERVICES LOYSVILLE, TYRONE TOWNSHIP, PERRY COUNTY, PA			
DETAILS - ELECTRICAL			
VERIFY SCALE BAR IS ONE (1) INCH LONG ON ORIGINAL DRAWING: 0 1 IF BAR IS NOT ONE (1) INCH LONG, ADJUST SCALE ACCORDINGLY		CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS. VARIANCE FROM CONTRACT DOCUMENTS NOT PERMITTED WITHOUT PROFESSIONAL & BUREAU OF CONSTRUCTION APPROVAL.	DRAWN BY S. SMOLKO CHECKED BY S. MULHOLLEN DATE 27 JUNE 2023 SCALE AS NOTED SHEET No. E-602