


THIS DRAWING AS AN INSTRUMENT OF SERVICE, IS THE PROPERTY OF THE ARCHITECTS, AND MAY NOT BE REPRODUCED WITHOUT THEIR PERMISSION AND UNLESS THE REPRODUCTION CARRIES THEIR NAME AS ARCHITECTS.

DUE TO DISTORTION FROM REPRODUCTION PROCEDURES, DIMENSIONS SHALL NOT BE SCALED FROM THE DRAWING, ONLY DIMENSIONS AS SHOWN SHALL BE VALID.


CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AT THE SITE BEFORE PROCEEDING WITH THE WORK.



1 FLOOR PLAN - LIGHTING
E2.0 SCALE: 1/4" = 1'-0"

LIGHTING SCHEDULE					
MARK DESCRIPTION	MANUFACTURER	MODEL	VOLTS	WATTS	NOTES
A	4" RECESSED LIGHTS	JUNO	WF4 LED 30K40K50K Mvolts 90CRI MW	120 28	FIXTURES IN EVE ON SIDE OF BUILDING HALO, RAB
B	6" RECESSED LIGHTS	JUNO	WF6 LED 27K30K35K Mvolts 90CRI MW	120 28	INTERIOR RECESSED FIXTURE FLAT CEILING (SET TO 35K) OR EQUAL - HALO, RAB
C	6" GIMBAL	JUNO	WF6 ADJ LED 27K30K35K Mvolts 90ZCRI MW	120 28	MEETING ROOM SLOPED CEILING (SET TO 35K) OR EQUAL - HALO, RAB
D1	1x4 FLAT PANEL LED	LITHONIA	CPANL 1x4 AOL1 SWW7 M4/DCMK14	120 40	OFFICE LIGHTING (SET TO 5K) OR EQUAL
D	2x4 FLAT PANEL LED	LITHONIA	CPANL 2x4 AOL6 SWW7 M2/DCMK224	120 40	OFFICE LIGHTING (SET TO 5K) OR EQUAL
EM	WALL MOUNTED LED WALLPACK	RAB	SLIM 18	120 40	WALL PACK ON FRONT AND REAR OF BUILDING
F	DECORATIVE LIGHT FIXTURE	MODERN FORMS	PD-55024	120 40	REFER TO MANUFACTURE FOR SPECIFICATIONS AND INSTALLATION REQUIREMENTS

KEYED NOTES	
①	ALL NEW LIGHTING IN THIS AREA SHALL BE WIRED TO EXISTING LIGHTING CIRCUIT AND CONTROL DEVICE MADE AVAILABLE DURING DEMOLITION.
②	ALL NEW EXIT SIGNS SHALL BE PROVIDED WITH EMERGENCY BATTERY BACKUP AND WIRED TO LOCAL LIGHTING CIRCUIT AHEAD OF LIGHTING CONTROL DEVICE.
③	EXISTING AREA TO REMAIN AS IS, NO NEW WORK.



SCHILLACI ARCHITECTS LTD.
MARK SCHILLACI 717.951.7466 SCHILLACIARCHITECTS.COM
KYLE SCHILLACI 717.875.8035 KSCHELLACI138@GMAIL.COM

141 N. Reamstown Rd.
Stevens, PA 17578
WWW.SCHILLACIARCHITECTS.COM

ELIZABETH TOWNSHIP
Addition / Renovations
to an Existing Building
423 Southview Drive
Lititz, PA 17543

FLOOR PLAN LIGHTING

REVISIONS:
DATE DESCRIPTION

ISSUED: 03/22/2023

E2.0

