

Issue Date: December 7, 2023

ADDENDUM NO. 2

MI-1213 PUCILLO HVAC RENOVATION

I. PURPOSE:

- A. Addenda shall make revisions, additions and/or deletions, and clarifications to the bidding documents dated November 17, 2023, for the project referenced above. Bidders shall review the Addendum in detail and incorporate any effects the Addendum may have in their bid proposal.
- B. Acknowledgement: Bidders shall acknowledge receipt of any and all Addenda in the technical proposal. All requirements of the bidding documents remain unchanged except as cited herein.

II. PROJECT MANUAL:

- A. None

III. QUESTIONS/CLARIFICATIONS:

- A. Does the HVAC equipment have factory disconnects or must the EC provide the disconnects?

Response: Provide disconnect switches as indicated in the mechanical equipment connection schedule on Drawing E-701.

- B. Question: The panel schedule for HBBR the VAV's are on 30amp breakers. Drawing E-701 mechanical equipment schedule note 4 states to provide a 25 amp breaker for VAV 7-5. Also in the MOCP section it has 25amp. Can you please clarify what size breaker is required for VAV's?

Response: Provide 30A-3P breaker as indicated in panelboard HBBR schedule. All disconnect switches associated with the VAV's are indicated to be provided with 25A fuses that would meet the MOCP requirements noted on the equipment schedule on Drawing H-701.

Question: You have a Device Programming Unit listed as one of the components of the fire alarm system, but the spec is not clear as to if we are to provide one to the owner as part of this fire alarm package. Do you want us to provide a Siemens Fire Alarm Device programmer to be turned over to the owner as part of this project?

Response: No, A programmer is not required. Specification Section 283111, Paragraph 2.3.D is deleted.