

LIGHTING CONTROL NOTES:

- IN SPACES WITH WALL BOX OCCUPANCY SENSORS SET TO MANUAL ON/AUTOMATIC OFF WITH 5 MINUTES DELAY TO OFF.
- IN SPACES WITH CEILING MOUNTED OCCUPANCY SENSORS AND LOW VOLTAGE WALL STATIONS (WITH OR WITHOUT DIMMING) SET TO MANUAL ON/AUTOMATIC OFF WITH 10 MINUTES DELAY TO OFF.
- IN SPACES WITH CEILING MOUNTED OCCUPANCY SENSORS SET TO AUTOMATIC ON/AUTOMATIC OFF WITH 10 MINUTES DELAY TO OFF.

SPECIFIC NOTES - ELECTRICAL NEW

E3	REINSTALL VIDEO CAMERA AND RECONNECT TO MATCH EXISTING.
E5	CONNECT TO EXISTING LIGHTING CIRCUIT SERVING SPACE.
E6	PROVIDE DEVICE AS SHOWN IN EXISTING BACKBOX.
E10	CONNECT TO NEAREST 120V RECEPTACLE CIRCUIT IN BUILDING.
E11	CONNECT TO EXISTING UNSWITCHED EMERGENCY LIGHTING CIRCUIT IN SPACE.
E17	LIGHTS NOT TO BE ON AUTOMATIC ON/OFF CONTROL IN ROOM.
E18	SWITCH FOR CONTROL OF FACULTY SHOWER 118 LIGHTING.
E19	REINSTALL SMOKE DETECTOR AND RECONNECT TO MATCH EXISTING.
E20	SWITCH FOR CONTROL OF SHOWER ROOM 129 LIGHTING.
E21	SWITCH FOR CONTROL OF WHIRLPOOL 130 LIGHTING.
E22	SWITCH FOR CONTROL OF MEN'S SHOWER ROOM 140 LIGHTING.

This drawing is the property of Century Engineering and is prepared for the exclusive use of its clients at the location indicated. No other use is authorized or intended.

CENTURY ENGINEERING
A Kleinfelder Company
10710 Gilroy Road
Hunt Valley, MD 21031
Phone: (443) 585-2400
www.centuryeng.com
© 2021 ALL RIGHTS RESERVED

SEAL

NO.	DESCRIPTION	DATE
REVISIONS		

MILLERSVILLE UNIVERSITY

MI-1213 PUCILLO HVAC RENOVATION


126 PUCILLO DRIVE MILLERSVILLE, PA. 17551

SHEET TITLE

**FIRST FLOOR
PLAN -
ELECTRICAL**

ISSUE DATE: 11.17.2023
DRAWN: SP DESIGNED: SGH CHECKED: SGH
SCALE: SHEET NO.
AS NOTED
PROJECT NO. E-102
24000543.001A

1 FIRST FLOOR PLAN - ELECTRICAL
1/8" = 1'-0"



GRAPHIC SCALE 1/8"=1'-0"

